



Modular Installation with Raised Access Floor Panels

INSTALLATION

160 South Industrial Blvd.
Calhoun, GA. 30701
MohawkGroup.com

Technical Services Department
508 East Morris St.
Dalton, GA 30721
800.833.6954
product_tech@mohawkind.com



For installation of The Mohawk Group modular carpet on raised access floor panels, our Modular Installation Guidelines must be followed. The installation should begin with the carpet tiles overlapping the access panel joints which will allow for a more consistent installation. Installing tiles flush or one to one with the panels may create more visible seams.

Additionally, all access panels should be sound, level and edges firmly secured to the raised flooring pedestals. If the panels are not secured properly the integrity of the installation and tiles installed will be adversely affected. Failing to follow these instructions will void The Mohawk Group Modular warranty.

For further information and to answer questions you may have, please contact The Mohawk Group's Field and Technical Services Department at 800 553 6045.